

# ICAR - Directorate of Weed Research (M.P.)

File No. 13-61/Works/2016-17

Date : 09/02/2018

## Corrigendum

**Tender Title :** Tender document for RCC Heavy duty floor with 6 inches thickness at Implement Shed of ICAR-DWR (Revised)

**Due Date :** 19/02/2018 at 2.30 pm

**Tender ID :** 2018\_ICAR\_288201\_1 dated 09-Feb-2018

With reference to above tender ID and tender title kindly read RCC to PCC. Corrected specification is as follows.

Sl.	Particulars of work	Quantum of work
1	PCC Heavy duty floor with 6" thickness (1:2:4) mix. C:S:A including proper slope should be given on both the side to match existing floor/level as per CPWD Specification with fine finishing on top surface by plastering with cement sand mixture (4:1) including labour charges complete in all respect.	34' x 28' x 6" = 476 cuft. Approx

Tender

  
I/c Works

  
Chairman works