



भा.कृ.अनु.प. - खरपतवार अनुसंधान निदेशालय

ICAR - Directorate of Weed Research

महाराजपुर, अधारताल, जबलपुर - 482004, (म. प्र.), भारत
Maharajpur, Adhartal, Jabalpur 482 004 (M.P.), INDIA



EPABX : +91-761-2353101, 2353934
Fax : 0761 - 2353129

Gram : WEEDSCIENCE
Email : dirdwsr@icar.org.in

F.No. : 13-138/Works/2015-16

Dt. : 21-03-2016

To,

Sub.-: Construction of Entrance Gate of Farm Godown – reg.

Dear Sir(s)

On behalf of the Director of this Directorate, Quotation are invited for Construction of Entrance gate of Farm godown as mentioned below:-

Sealed quotations are invited for the necessary work as per details given below.

S.no	विवरण	लगभग माप
1	पहले से बनी दीवार व बीम को अच्छी तरह से तोड़ने का कार्य सभी संबंध में मय मजदूरी के	Beam 11.66' X 0.75' x 0.75' = 6.56 cuft Wall- 12' x 8.5' x 9" = 76.5 cuft
2	RCC (1:2:4) बीम को बेस्ट क्वालिटी Ø12mm रेनफोर्समेंट स्टील का प्रयोग करते हुये, पहले से बने कॉलमों में दोनो तरफ अच्छी तरह से कॉलमों को पंचर करके रॉड को फसाकर बीम डालने का कार्य व बीम को दोनो तरफ से प्लास्टर कर पूर्ण फिनिशींग के साथ, व पहले से बनी दीवार को मैच करते हुये उचित रंग की पुताई दो या तीन कोट पूर्ण फिनिशींग होने तक का कार्य सभी संबंधों में मय मजदूरी के (Including Centering & Shuttering reinforcement or as per CPWD Specification)	11.66' X 0.75' x 0.75' = 6.56 cuft
3	बेस्ट क्वालिटी मानक कम्पनी की बनी हुई 20 गेज, जी.आई. मटेरिल से बनी मोटराईज्ड/मैन्युअल गेयर वाली रोलिंग षटर प्रक्षेत्र भण्डार की दीवार में अन्दर की तरफ से बेस्ट क्वालिटी स्प्रिंग नट,बोल्ट,वाषर आदि से अच्छी तरह फिक्स कर षटर लगाने एवं 2 कोट पेन्ट करने का कार्य सभी संबंधों में मय मजदूरी के (मोटराईज्ड एवं मैन्युअल गेयर वाली दोनो षटरों के रेट अलग अलग कोट करें)	H 12' x W 8.5' = 103.2 sqft Opening Space 12' height x 8.5' wide Clear Space प्रवेश हेतु आवष्यक है ट्रैक्टर मय लोडेड ट्राली के गोडाउन में आसानी से प्रवेश हो जाए इसलिए षटर का ऊपरी बाक्स तथा साईड की स्लाईडिंग दिवाल के फेस से अन्दर ही होना चाहिए
4	प्रक्षेत्र भण्डार की दीवार की बीम जिसकी लम्बाई लगभग 13 फुट है पर पहले से लगी विद्युत वायर फिटिंग को निकाल कर लगाने वाले षटर के ऊपर षिपट करने का कार्य सभी संबंधों में मय मजदूरी के सामग्री इत्यादि सहित (इन्डस्ट्रीयल वायरिंग के तरह चिन्तारी मुक्त जोड वाली होनी चाहिए)	One Job
5	प्रक्षेत्र भण्डार की दीवार पर दरवाजे के ऊपर मानक कम्पनी की over hanging shead बेस्ट क्वालिटी जी.आई. मटेरियल व प्रोपर गेज की प्रोफाईल शीट का प्रयोग करते हुये, बेस्ट क्वालिटी नट,बोल्ट,वाषर आदि से अच्छी तरह फिक्स over hanging कर छज्जा/षेड बनाने का कार्य, कम से कम तीन रूफ कैंची एवं पर्लान लगाकर उच्च दाब वाली हवा में भी टिकाउ, सभी संबंधों में मय मजदूरी के	Over hanging shed (Chajja) Size L-6' x w-12' = 72 sqft रूफ ट्रेस कैंची-3 नग (संलग्न ड्राईंग के अनुसार) प्रोफाईल शीट साईड 2.5' x 6.5' की 6 नग शीट
6	कार्य के दौरान होने वाले अन्य कार्य को करना होगा। जिसका अलग से कोई भुगतान देय नहीं होगा।	

नोट:- 1. ठेकेदार कोटेशन देने के पूर्व स्थल निरीक्षण अवष्य कर ले। 2. उपयोग में आने वाला मटेरीयल उच्च (quality) गुणवत्ता का व स्टेण्डर्ड कम्पनी का होना चाहिए तथा मटेरियल लगाने के पूर्व सेम्पल को निर्माण समिति से अनुमोदित करा कर कार्य में लगाया जाना अनिवार्य होगा। 3. ठेकेदार कार्य आदेश में दी गई कार्य की मात्रा के अनुसार कार्य करें मात्रा लिखित मात्रा से अधिक होने की संभावना होने पर पूर्व में सक्षम अधिकारी से लिखित अनुमति प्राप्त कर के ही आगे का कार्य करें, 4 ठेकेदार कार्य प्रारम्भ करने के पूर्व सम्बन्धित अनुभाग की अनुमति प्राप्त करउ कार्य प्रारम्भ करें। उपरोक्त सम्पूर्ण कार्य का रेट प्रति वर्गफुट व प्रति रनिंग फुट में देने का श्रम करें, लमसम रेट स्वीकार नहीं होगा। क्योकि सिविल वर्क कम या अधिक होने की संभावना बनी रहती है।

ड्राईंग संलग्न है:-

Cont.

Terms and conditions

- 1 The rates should be quoted F.O.R. Destination Directorate DWR, Campus at Maharajpur, Jabalpur.
- 2 Rates of Sales Tax, Service Tax and other taxes liable should be indicated in clear terms separately. Sales Tax Registration Number both under state and Central Tax Act/Rules should be specifically indicated.
- 3 Tax Deduction at Source (TDS), If applicable, will be made from the Bill of your Firm/Agency.
- 4 Unless otherwise mentioned in the quotation, it will be presumed that the quoted rates are inclusive of all taxes/levies.
- 5 The work should be done in accordance with CPWD specifications.
- 6 The rates quoted should be valid for 90 days from the date of opening of quotation and it should include packing, forwarding and transportation charges.
- 7 There should be no cutting/overwriting. The cuttings if any should be duly attested. Unattested/ amended/ overwritten figures will not be considered.
- 8 In all matters of disputes, the decision of the Director of this Directorate shall be final.
- 9 Payment will be made within reasonable time say within 30 days after the certified of works at this Directorate. Since the mode of payment will be e-payment system, hence Bank Account Number, Address and IFSC Code Number of Bank must be mentioned in the bill/invoice.
- 10 Quotation should be sent in a sealed cover (BY REGD. POST/SPEED POST/COURIER/UPC/TENDER BOX DWR Jabalpur) and the covering containing. Quotation Construction of Entrance gate of Farm godown at DWR. By **11/04/2016** on or before **3.00** pm Quotation received in an unsealed cover or received after the due date and those which are ambiguous are liable to be rejected. Quotation will be opened on the same day at 3.30 P.M. While opening the quotation an authorized representative of the firm may be present.
- 11 **The bid security (EMD) amount equal to 2% of the quoted price** must be submitted along with the bid in form of Demand Draft/Banker's cheque/FDR drawn in favour of **ICAR UNIT- DWSR, JABALPUR** otherwise the bid will not be taken into consideration.
- 12 This Directorate reserves the right to reject any or all the quotation(s) received without assigning any reason thereof.
- 13 All disputes subject to Jabalpur Jurisdiction only.
- 14 All communication must be addressed to the undersigned by DESIGNATION ONLY and not by name.
- 15 The Directorate will not be responsible for providing any compensation with respect to medical injuries from implement, tools, snake bite, any kind of accidents or death of labour workers while working in the Directorate premises. The contractor should make his own arrangement for providing medical, first aid, etc to his laborers.
- 16 Before giving or sending the Quotation the contractor may visit the site to better understand the clear requirement.
- 17 The contractor must have and attach the copy of all the required documents related to registration as well as TIN & PAN No. etc.-
- 18 All the rates quoted should be on rft/sqft/cuft. Basis only. The quantum of work may vary. No extra payment will be given for any small work raised during on going work which is not mentioned in the estimate.
- 19 No Special arrangement/facilities will be provided to the Contractor whatsoever will be available on the site may be permitted as per term and condition of quotation by C.A.
- 20 Before starting the work contractor should take necessary permission from the concerned Section. The sample of poofiles sheet and other materials invalved will be approved by works committee before fixing.

Encl : Drawing

Yours faithfully,

I/c Store & Purchase section

Drawing

