



भा.कृ.अनु.प. - खरपतवार अनुसंधान निदेशालय

ICAR - Directorate of Weed Research

महाराजपुर, अधारताल, जबलपुर - 482004, (म. प्र.), भारत
Maharajpur, Adhartal, Jabalpur 482 004 (M.P.), INDIA



EPABX : +91-761-2353101, 2353934

Email : dirdwsr@icar.org.in

Fax : 0761 - 2353129

F.No. : 13-160/ Works/2016-17

Date: 08-02-2018

प्रति,

विषय: निदेशालय के अवशेष रसासन विज्ञान प्रयोगशाला (द्वितीय) (Room No. 15) के रिपेयर एवं रखरखाव कार्य के सम्बंध में।

महोदय,

निदेशक, ख.अनु.निदेशालय की ओर से निदेशालय के अवशेष रसासन विज्ञान प्रयोगशाला, द्वितीय (Room No. 15) के रिपेयर एवं रखरखाव कार्य कराने की आवश्यकता हेतु सील बंद निविदा/ऑफर पोस्ट के द्वारा आमंत्रित है। विवरण निम्नानुसार है :-

S/No.	Particulars of work	Quantum of work approx.
1	Providing and fixing of Granite top and horizontal, vertical wall strips 16 mm thick standard quality black colour mirror polish on wall attached platform with labor charges etc. (fixing of granite should be done with proper adhesive) (Old Platform top should be excavated)	131 sqft.
2	Providing and fixing of Wall Tiles of proper 8 mm thick, standard quality, branded make like Johnson/kajiria etc light colour mirror finish on platform/central working table walls with labor charges etc. (fixing of Tiles should be done with proper adhesive) Complete in all respect.	49 sqft
3	Providing and fixing of Verified floor Tiles of proper thick, standard quality, branded make like Johnson / kajiria or equivalent quality etc light colour mirror finish on laboratory floor including inner portion of platform/Central working table, 6" high Skirting on walls with proper exavation and labor charges etc. (fixing of Tiles should be done with proper adhesive) Complete in all respect.	380 sqft Skirting -45 rft 6" high
4	Providing and fixing of Swan neck Lab three way cock with labour charges, approved or highly best quality make complete in all respect.	3 Nos.
5	Repairing of existing wooden door panels/Frames in existing wall mounted cup boards, below the platform. with hinges, handles, latches, suitable locks and other required items, wooden polish two or more coats up to well finish. etc complete in all respect.	58.58 sqft with all required items.
6	Providing and fixing of door panels below the Central working Table cup boards of best quality laminated 18 mm Board of teak wood colour with wooden frame, hinges, handles latches, suitable locks and other required items etc below the Table for keeping material. Panting/polishing etc complete in all respect. (Two panels in each cupboard total 12 panels in 6 frames)	60 sqft.
7	Wall putty of branded make like Birla white/J.K. wall putty 2-3 coats and rubbing/finishing with sand paper to make wall surface smooth up to well finish for white washing complete in all respect.	822.86 sqft
8	Putting, repairing of cracks Surfacing white washing with best quality branded interior plastic emulsion paint of Asian/burger make two or more coat up to well finish. Complete in all respect with material and labor etc.	822.86 Sqft approx
9	Painting of window/Door frames/wall mounted rack Two or more coats, up two well finish with synthetic enamel paints of popular brand (Asian)colors to suit the location with clearing surfacing and removing rust, dust complete in all respect with material and labor etc.	302 sqft approx.
10	Other work as per requirement of Situation arises during the work. (With proper justification)	As required for quality work

नोट :- 1. ठेकेदार कोटेशन देने के पूर्व स्थल निरीक्षण अवश्य कर ले। 2. उपयोग में आने वाला मटेरियल उच्च (quality) गुणवत्ता का व स्टेण्डर्ड कम्पनी का होना चाहिए तथा मटेरियल लगाने के पूर्व सैम्पल को निर्माण समिति से अनुमोदित करा कर कार्य में लगाया जाना अनिवार्य होगा। 3. ठेकेदार कार्य आदेश में दी गई कार्य की मात्रा के अनुसार कार्य करें तथा मात्रा लिखित मात्रा से अधिक होने की संभावना होने पर पूर्व में सक्षम अधिकारी से लिखित अनुमति प्राप्त कर ही आगे का कार्य करें, 4 ठेकेदार कार्य प्रारम्भ करने के पूर्व सम्बन्धित अनुभाग की अनुमति प्राप्त कर कार्य प्रारम्भ करें। कार्य के दौरान भी निर्माण समिति को कार्य की प्रगति का अवलोकन कराया जाना आवश्यक है। उपरोक्त सम्पूर्ण कार्य का रेट प्रति वर्गफुट, व रनिंग फुट में देने का श्रम करें, लमसम रेट स्वीकार नहीं होगा। यदि स्कारटींग के रेट रनिंग फुट में पात न होने पर उसके वर्गफुट रेट से ही गणना की जावेगी।

नोट :-

1. ठेकेदार कोटेशन देने के पूर्व स्थल निरीक्षण अवश्य कर ल।
2. उपयोग में आने वाला मटेरियल उच्च गुणवत्ता का व स्टेण्डर्ड कंपनी का होना चाहिये तथा मटेरियल लगाने के पूर्व सम्पल को निर्माण समिति से अनुमोदित कराकर कार्य में लगाया जाना अनिवार्य होगा।
3. ठेकेदार कार्य आदेश में दी गई कार्य की मात्रा के अनुसार कार्य करें तथा मात्रा लिखित मात्रा अधिक होने की संभावना होने पर पूर्व में सक्षम अधिकारी से लिखित अनुमति प्राप्त कर ही आगे का कार्य करें।
4. ठेकेदार कार्य प्रारंभ करने के पूर्व संबंधित अनुभाग की अनुमति प्राप्त कर कार्य प्रारंभ करें। कार्य के दौरान भी निर्माण समिति को कार्य की प्रगति का अवलोकन कराया जाना आवश्यक है। उपरोक्त सम्पूर्ण कार्य का रेट प्रति वर्गफुट, रनिंग फुट में देने का श्रम करें, लमसम (एकमुश्त) रेट स्वीकार नहीं होगा।

नियम एवं शर्तें :-

1. दरों का उल्लेख वस्तु को इस निदेशालय परिसर, महाराजपुर, जबलपुर पहुंचाने तक का होना चाहिये।
2. सेल्स टेक्स अथवा अन्य टेक्स का स्पष्ट रूप से उल्लेख होना चाहिये यदि टेक्स का उल्लेख नहीं रहता है, तो यह माना जावेगा कि दर्शायी गई दरों में टेक्स सम्मिलित है। इस निदेशालय से कोई "सी" अथवा "डी" फॉर्म जारी नहीं किया जाता है।
3. बिलों से टी.डी.एस. यदि लागू हो तो कटौती निम्नानुसार की जावेगी।
4. दर्शायी गई दरों की वैधता निविदा खोलने की तिथि से कम से कम 90 दिनों तक की होनी चाहिये, दरों में पैकिंग forwarding एवं ट्रांसपोर्टेशन चार्ज स्पष्ट रूप से उल्लेख होना चाहिये।
5. सम्पूर्ण रूप से पूर्ण सीलबंद निविदा/कोटेशन निदेशालय में रखी निविदा पेटी या पोस्ट के द्वारा **दिनांक 28/02/2018 दोपहर 2.30** बजे तक स्वीकार की जावेगी। फर्म इस पर ध्यान दें, कि किसी भी प्रकार अस्पष्ट, मिटी हुई, सफेदी लगी लिखाई नहीं होनी चाहिये, यदि कोई कटिंग अन्य ओवर राईटिंग होती है, तो उसे सत्यापित (उस स्थान पर हस्ताक्षर होना चाहिये) अन्यथा ऐसी दशा में कोटेशन पर कोई विचार नहीं किया जावेगा।
6. सभी मामलों में निदेशक, ख.अनु. निदेशालय का निर्णय अंतिम होगा तथा निविदाकारों को मान्य होगा।
7. बिल का भुगतान 30 दिनों में किया जावेगा। चूंकि भुगतान ई-पेमेंट के द्वारा किया जाता है, इसलिए फर्म का बैंक खाता नं. पता एवं आई.एफ.एस.सी. कोड बिल में स्पष्ट रूप से उल्लेखित किया जाना चाहिये।
9. **निविदा/कोटेशन में रु. 5,000/- की राशि बतौर धरोहर राशि (ई.एम.डी.) के रूप में एकाउंट पेई डिमांड ड्राफ्ट/पे. आर्डर ICAR UNIT DWR, JABALPUR के पक्ष में देय हो आवश्यक रूप से निविदा/कोटेशन के साथ संलग्न होना चाहिये। अन्यथा निविदा पर विचार न करते हुये रद्द कर दिया जावेगा। धरोहर राशि (ई.एम.डी.) की राशि स्माल स्केल इंडस्ट्रीज के लिए छूट है। इस हेतु निविदा के साथ वांछित प्रमाण पत्र के संलग्न करना अनिवार्य है।**
11. निदेशक, ख.अनु. निदेशालय के पास यह अधिकार सुरक्षित है, कि कोई भी निविदा/कोटेशन को स्वीकार अथवा अस्वीकार बिना किसी कारण के किया जा सकेगा।
12. किसी भी प्रकार के पत्राचार अधोहस्ताक्षरकर्ता के पद नाम से ही किया जावे न कि उसके नाम से।
13. **सभी संलग्न Annexure भरना अनिवार्य है।**
14. किसी भी प्रकार का विवाद जबलपुर न्यायालय (jurisdiction) के अधीन रहेगा।
15. फ्लोरींग कार्य हेतु रेटा अच्छी गुणवत्ता वाली एवं सीमेंट ए.सी.सी या उसके समतुल्य कम्पनी वाली उचित गोड की लगाना आवश्यक है।
16. केन्द्र सरकार के लेबर संबंधित सभी नियमों का पालन करने की जिम्मेदारी ठेकेदार की ही होगी।
17. **सफल निविदाकर्ता को कार्य आदेश देने के पूर्व सम्पूर्ण वर्क आर्डर राशि के 10 प्रतिशत की सुरक्षा राशि जमा करना होगा।** (उक्त एस.डी.) जमा होने पर ई.एम.डी. लौटाने पर विचार किया जायेगा।

प्रभारी क्य एवं भण्डार अनुभाग

Essential Basic Information

1	Name of the Firm/Agency	
2	Full address with Tele./Mob. No., Fax No., e-mail	
3	Details of Tender Fee & EMD (DD/No., date, Name of the Bank/Branch)	
4	Registration Certificate of the Firm/Company	
5	GST Registration no.	
6	I.T. PAN No./ TIN No.	
7	Proprietary Certificate /Authorized dealer certificate	
8	Bank Details	
	Name of the Account Holder /firm/ Company (Payee's Account Name)	
	Nature of Account (saving/current)	
	Name of the Bank	
	Bank Account No.	
	Branch Address	
	IFSC Code of Bank/Branch	
9	Check List	

Date

Place

Name of the Authorized Signatory

Stamp & Signature

TECHNICAL CUM FINANCIAL BID

Tender Ref :

Date :

Sl	Particular of Work	Approx Area	Rates	Cost (Rs.)
1	Providing and fixing of Granite top and horizontal, vertical wall strips 16 mm thick standard quality black colour mirror polish on wall attached platform with labor charges etc. (fixing of granite should be done with proper adhesive) (Old Platform top should be exavated)	131 sqft.		
2	Providing and fixing of Wall Tiles of proper 8 mm thick, standard quality, branded make like Johnson/kajiria etc light colour mirror finish on platform/central working table walls with labor charges etc. (fixing of Tiles should be done with proper adhesive) Complete in all respect.	49 sqft		
3	Providing and fixing of Verified floor Tiles of proper thick, standard quality, branded make like Johnson / kajiria or equivalent quality etc light colour mirror finish on laboratory floor including inner portion of platform/Central working table, 6" high Skirting on walls with proper exvation and labor charges etc. (fixing of Tiles should be done with proper adhesive) Complete in all respect.	380 sqft Skirting -45 rft 6" high		
4	Providing and fixing of Swan neck Lab three way cock with labour charges, approved or highly best quality make complete in all respect.	3 Nos.		
5	Repairing of existing wooden door panels/Frames in existing wall mounted cup boards, below the platform. with hinges, handles, latches, suitable locks and other required items, wooden polish two or more coats up to well finish. etc complete in all respect.	58.58 sqft with all required items.		
6	Providing and fixing of door panels below the Central working Table cup boards of best quality laminated 18 mm Board of teak wood colour with wooden frame, hinges, handles latches, suitable locks and other required items etc below the Table for keeping material. Panting/polishing etc complete in all respect. (Two panels in each cupboard total 12 panels in 6 frames)	60 sqft.		
7	Wall putty of branded make like Birla white/J.K. wall putty 2-3 coats and rubbing/finishing with sand paper to make wall surface smooth up to well finish for white washing complete in all respect.	822.86 sqft		
8	Putting, repairing of cracks Surfacing white washing with best quality branded interior plastic emulsion paint of Asian/burger make two or more coat up to well finish. Complete in all respect with material and labor etc.	822.86 Sqft approx		
9	Painting of window/Door frames/wall mounted rack Two or more coats, up two well finish with synthetic enamel paints of popular brand (Asian)colors to suit the location with clearing surfacing and removing rust, dust complete in all respect with material and labor etc.	302 sqft approx.		
10	Other work as per requirement of Situation arises during the work. (With proper justification)	As required for quality work		

Terms and condition

1. Rates are Inclusive all Taxes (GST and all)
2. Quotation validity : 90 days
3. Others

Date

Place

Name of the Authorized Signatory

Stamp & Signature

**Details of the Minimum 2 (two) years experience/work done
(PLEASE ATTACH DOCUMENTRY PROFF)**

Sr. No	Name of the Deptt/Organization & name of Contact Person with Ph. No.	Period		Work details	Remark
		From	To		

(Authorized Signatory)